

CONCRETE DELIVERY STANDARD

PURPOSE

1. The general purpose of the Concrete Delivery Standard is to avoid damage to existing sidewalks and landscape.

GENERAL

1. This standard shall apply to all projects.

EXECUTION

Concrete delivery trucks are to remain on paved streets or parking lots. Any concrete delivery that cannot be accomplished in this manner shall be delivered to the job site utilizing a concrete delivery buggy or by a pumping operation.

If either of these methods is prohibitive, alternate delivery routes shall be reviewed and approved by the CMU Project Manager. The delivery trucks shall not drive across lawn areas or sidewalks without prior approval by the CMU Project Manager and/or The Director of Plant Engineering and Planning. Any repair work resulting because of not adhering to this standard shall be paid by the contractor/person responsible.

CONCRETE DELIVERY STANDARD

DOCUMENT CONTROL PAGE:

Document Published:	September 8, 2006
Prepared By:	Dan Methner
Reviewed By:	Linda Slater, John Latoski, Stan Mandziuk, Don McIntyre, Bob Ringel, Jim Jocks, Jay Kahn, John Dillon, Tom Burke, Tom Prekert, Crissy Trevino
Approved By:	Steve Lawrence

Revision History:

Date	Revision	Approved By:
1.30.07	Revised to include all concrete deliveries. Re-named (formerly known as: Sidewalk Concrete Delivery Standard)	Steve Lawrence